

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>49N</u> R <u>15W</u>	<u>NW-SE 1/64</u>
	S <u>19-20</u> T <u>49N</u> R <u>15W</u>	<u>N-S 1/64 19-20</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 05/12/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(NW-SE 1/64) The Center of the NW1/4 of the SE1/4, Section 19. Not established in the original survey.

(N-S 1/64 bet. Sections 19 and 20) The SE corner of the N1/2 of the NE1/4 of the SE1/4 of Section 19. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(NW-SE 1/64) Established the corner at the intersection of straight lines connecting opposite 1/64 corners.

(N-S 1/64 bet. Sections 19 and 20) Established the corner midway and on the Section line between Quarter corner C8 662.14' north and 1/16 corner #14 Sec. 19 662.14' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

NW-SE 1/64 SEC. 19

N-S 1/64 BETWEEN 19 AND 20

Set 1"IDx36" I.pipe w/4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 10" W.Pine N55E 44.45' mrkd "1/64 BT"  
 14" R.Pine N27W 6.95' do  
 11" W.Pine S13W 5.05' do  
 10" R.Pine S45E 48.40' do  
 Bearings are magnetic.

Set 1"IDx36" I.pipe w/4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 5" R.Pine S04E 13.65' mrkd "1/64 BT"  
 8" J.Pine N85W 23.0' do  
 11" J.Pine N01E 20.3' do  
 15" R.Pine N53E 45.25' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/18/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

