

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19-20</u> T <u>49N</u> R <u>15W</u>	<u>S-N 1/64 19-20</u>
	S <u>20</u> T _____ R <u>15W</u>	<u>C-S-NW 1/64</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 05/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(S-N 1/64 between Sections 19 and 20) The NW corner of the S1/2 of the SW1/4 of the NW1/4, Section 20. Not established in the original survey.

(C-S-NW 1/64) The NE corner of the S1/2 of the SW1/4 of the NW1/4 of Section 20. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(S-N 1/64 between Sections 19 and 20) Established the corner midway and on the Section line between Quarter corner C8 661.26' south and 1/16 corner #3 Sec. 20 661.26' north.

(C-S-NW 1/64) Established the corner midway and on a straight line between 1/16 corner #4 Sec. 20 660.23' north and 1/64 corner 660.23' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

S-N 1/64 BETWEEN 19 AND 20

C-S-NW 1/64, SECTION 20

Set 1"IDx36" I.pipe w/4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 13" R.Pine S01E 29.45' mrkd "1/64 BT"
 13" R.Pine S39W 35.75' do
 6" R.Pine N24W 4.1' do
 11" R.Pine S61E 21.8' do
 Bearings are magnetic.

Set 1"IDx36" I.pipe w/4" alum MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" J.Pine S03W 13.2' mrkd "1/64 BT"
 9" J.Pine S62W 11.8' do
 10" J.Pine N32W 24.25' do
 10" J.Pine S85E 7.55' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/18/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division