

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 49N R 15W	15
	S 19 T 49N R 15W	C-S-SW 1/64
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on Jan-64 05/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(15-Sec. 19) West 1/16 corner between Sections 19 and 30. Not established in the original survey.

(C-S-SW 1/64) The NW corner of the S1/2 of the SE1/4 of the SW1/4 of Section 19. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(15-Sec. 19) Established the corner on the Section line between Section corner 1279.95' west and Quarter corner 1315.47' east, being 20.00 chains, proportionate to the original plat, west of the Quarter corner.

(C-S-SW 1/64) Established the corner midway and on a straight line between 1/16 corner #15 660.75' south and the calculated position of 1/16 corner #11 660.75' north.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" Maple S35E 16.0' mrkd "W1/16 BT"  
 10" R.Pine N45E 22.5' do  
 9" R.Pine N09E 25.5' do  
 12" R.Pine N77W 29.95' do  
 Bearings are magnetic.

(C-S-SW 1/64) Set 1"IDx36" I.P. w/4" alum MDNR cap. Set measuring nail with MDNR tag in the side of:  
 14" R.Pine S74E 3.9' mrkd "1/64 BT"  
 5" R.Pine S01E 14.2' do  
 5" R.Pine N61W 14.15' do  
 9" R.Pine N15E 27.8' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/18/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division