

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 15W


Alger COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner between Sections 16-17

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 8-17-62

WITNESSES TO CORNER..... 14" Red Pine ($\frac{1}{4}$ S NBT) S10°E 37 links



13" red pine ($\frac{1}{4}$ S NBT) S82°W 14 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner replaced from one Y. Pine B.T. bearing S73°W 12 links. B.T. is a stump with lower face, notch and scribe marks in evidence.
Corner lies on east slope of hill adjacent to spruce swamp.
Corner lies 05 links west and 12 links north of 40.00 chains.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE March 7, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler