

Approved by Alger County
Land Survey Reorganization
Peer Group Under Act 343 of
P.A. of 1930 On 3-24-1997

Gerald Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

5-24

For corners in
ALGER
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 49N R 14W K3
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
TIME 2:00 pm

MAR 31 1997

DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on October 18, 1996, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K3: PLS - Geo. E. Adair, DS, 1851, Set post at corner of Sections 1-2-11 & 12 * Beech 13, N.15 W., 17 links * Sugar 8, S.39 E., 16 links **** James Roundtree, CS, 1908. * Iron post now driven according to field notes and barren trees. In cut in road running North and South, East and West. * 9" Cedar, 69 links, S.W. of post, at corner of Schineder's farm. * 8 1/2" Cedar, S.E. of 69 1/2 links fence post now belonging to Wm. Leighton. **** Gerald W. Carlson, R.L.S., 1977. * Found 1" iron 1.5 feet West of centerline blacktop road in line with centerline of old road to West. * Guard post, S.86 W., 28.58 feet. * Guard post, N.82 W., 27.82 feet. * 9" W. Birch, N.57W, 29.10 feet. * 10" Maple, N.56 E., 42.95 feet. * Recorded in L.1, P.113, Alger County Records. **** Alger County Road Commission, Robert L. Jamros, R.L.S., 1991. * Corner position included and used as a alignment corner for the rehabilitation of Sable Lake Road from the Village of Grand Marais to Grand Sable Lake. * References of the 1977 report verified and used. **** No other subsequent restoration. ****

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron bar, 10" below road surface of new asphalt road. * In road cut and 2.3 feet West of Centerline of new pavement of North-South road and on centerline of old East-West road. * Verified existing references from 1977 report and monument material as found in 1991. Renewed existing references and added additional reference objects. Monument at existing corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced existing 1" Iron bar with 5/8" x 18" Rebar with Bernsten 3 1/4" Aluminum cap no. RBD 5325, stamped to identify corner position. * Renewed two existing reference trees and added two additional reference objects. * Set PK nails for measure w/Aluminum I.D. washers in the following reference trees. * Exist. BT, W.Birch 15", N.52 W., 29.17 feet, exist. lower blaze. * Exist. BT, Maple 10", N.60 E., 43.04 feet, exist. lower blaze. * Six foot steel fence post w/ survey marker sign, S.37 E., 46.96 feet. * Six foot steel fence post w/ survey marker sign, S.52 W., 38.58 feet. * All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849



Date 25 March 1997