

SURVEY & REMONUMENTATION

FEB 19 1998

05-89

Approved by _____
 Land Surveyor _____
 Peer Group Under Article 43 of
 P.A. of 1990 On 12-10-1997

Gerald W. Carlson
 Chairman

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____ <small>(County)</small>	Located in: _____	Corner Code # _____	
1. Public Land Survey	T <u>49</u> R <u>13</u>	<u>AG</u>	
	T <u>49N</u> R <u>14W</u>	<u>MG</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

FILED
 TIME 9:30 A.M.

DEC 17 1997

DONALD W. KINNUNEN
 REGISTER OF DEEDS
 BER COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Robert L. James, in a field survey on August 13, 1997, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A6: PLS - John Eurt, OS, 1841 * Set quarter section post * Beech 8, S.25 E., 16 links * Beech 13, N.25 W., 22 links **** George L. Depew, County Surveyor, 1917 * Set iron corner on true line at equal distance * No references given **** M.O.S.H., Survey and Construction Plans for M-77, 1958 * Corner position not shown, only wire fence to East **** Gerald W. Carlson, RLS, 1978 * Found 1/2 inch iron pipe at East edge of pavement of M-77, old broken fence to East and West * Witnesses - Maple 5, S.43 W., 32.71 feet * Triple Maple 5, S.38 W., 64.40 feet * Power Pole, N.13 E., 92.00 feet * Recorded in Liber 1, Page 175, Alger County Corner Records **** Neil E. Hill RLS, 1989 * Found 1/2 inch iron pipe on East edge of pavement and accepted, placed monument box * Witnesses - S.53 W., 75.70 feet, Maple * S.70 W., 61.76 feet, 11 Maple * West, 65.43 feet, 12 Maple * N.10 E., 92.27 feet, Power Pole * Recorded in Liber 4, Page 53, Alger County Corner Records **** No other subsequent restoration recorded.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A6: Found 1/2 inch Rebar w/I.D. cap no. 27447 (Neil E. Hill) in monument box, 11.6 feet East of centerline pavement on M-77 * Renewed exist. BT's and established additional references. * Measurements to corners North and South check well. Corner position is accepted and used locally. * Accepted monument at this position as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A6: Replaced 1/2 inch Rebar with a 5/8 inch by 18 inch Rebar w/Berntsen Alum. cap no. RBD 5325, stamped to identify corner position * Renewed exist. BT's w/BT signs and established additional references w/BT signs * Set PK nails w/Alum. I.D. washers for measure in the following * Exist. BT, Power Pole, N.14 E., 92.36 feet, scribed "BT" at base, no signs * Red Pine 16, S.42 E., 55.65 feet * Maple 14, N.83 W., 65.49 feet * Exist. BT, Maple 7, S.44 W., 92.57 feet * All bearings are magnetic.

Signed by Robert L. James
 Surveyor's Michigan License No. 25849

Date 12/10/1997

