

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------|---------------|
| <u>Alger</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 49N R 16W | M11 |
| | T 49N R 16W | K12 |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|----|---|----|---|----|---|---|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | 4 | | 3 | | 2 | | | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | 9 | | 10 | | 11 | | | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | 16 | | 15 | | 14 | | | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | 21 | | 22 | | 23 | | | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | 28 | | 27 | | 26 | | | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | 33 | | 34 | | 35 | | | 36 |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on K12 06/03/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(M11) Corner common to Sections 25-26 T49N-R16W and Sections 30-31 T49N-R15W. 1841 - Established by Wm.A.Burt Deputy Surveyor. Set post. Beech 14" N34E 30 links, Maple 8" N43W 59 links. 1948 - Remonumented by R.J.Brotherton RLS in the "old hole and portion of wood remains of old Govt. stake point. Found remains of Beech Gov't. B.T. in NE position...located actual notch of Govt. Fir Line tree just west of the corner". Set 1" iron and 4" pine post. 1953 NBTs: 14" Beech N25E 5.5 links, 8" Sugar S44 1/2E 30 links.

(K12) Quarter corner common to Sections 35-36. 1850 - Established by Wm.Ives Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Beech 7" N68W 38 links, Sugar 10" S38E 67 links. 1948 - Reestablished midway and on line between Section corners by R.J.Brotherton RLS. "Set Iron and 4" post. 8" Maple is N78W 27.0'. Corner comes in east rut of road and no old BTs were found."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(M11) The 1948 iron and post were not recovered. Remonumented the corner at record bearing and distance from the 1953 NBTs, both found in place. The Beech NE is standing dead. The Sugar SE is in good condition. The corner lies approx. 100' south of an E-W trail.

(K12) The original post and accessories were not recovered. Recovered Brotherton's iron - an iron leaf spring - S18W 0.62' from the proportionate position of record and accepted same as a careful and faithful reestablishment of the position of the corner. Brotherton's NBT Maple was not recovered. Drove a 5/8" capped rebar at the corner position. The leaf spring was left adjacent. The corner falls on the east edge of old road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(M11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
17" Maple S39E 20.38' mrkd "S31 NBT" 1948 NBT
7" Maple N70E 22.9' "S30 NBT"
21" Maple N43W 55.09' "S25 NBT"
11" Maple S87W 53.5' "S36 NBT"
Bearings are magnetic.
(K12) Set 5/8"x24" rebar with plastic MDNR cap. Set measuring nail with MDNR tag in the side of:
12" Maple N86E 32.56' mrkd "1/4S NBT"
8" Maple S13E 16.5' do
19" Hemlock N71W 53.37' do
9" W.Birch N06E 15.47' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/11/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

