

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T 49N R 16W	M10
2. Property Controlling in Section	S 25 T 49N R 16W S _____ T _____ R _____ S _____ T _____ R _____	7
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	7 04/08/2009	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on M10 04/08/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 25) North 1/16 between Section 25 T49N-R16W and Section 30 T49N-R15W. Not established in the original survey.

(M10) Quarter corner common to Section 25 T49N-R16W and Section 30 T49N-R15W. 1841 - Established by Wm.A.Burt Deputy Surveyor midway and on the Range line between Section corners 40.00 chains north and south. Set post. Hemlock 21" N36E 21 links, Hemlock 8" N31W 17 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 25) Established the corner midway and on the Range line between Quarter corner 1321.75' south and Section corner 1321.75' north.

(M10) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Range line between Section corners 2643.50' north and south. From the corner thus established, I found a 3/4" iron pin, not of record, lying on the ground surface, S20E 10' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx36" I.pipe with 4" alum. MNDR cap. Set measuring nail with MDNR tag in the side of:
 10" R.Pine S70E 17.63' mrkd "N1/16 BT"
 5" twin W.Birch S20W 11.29' do
 13" R.Pine N28W 33.15' do
 10" W.Birch N07W 50.85' do
 Bearings are magnetic.

(M10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" W.Pine S66E 11.9' mrkd "1/4S NBT"
 10" twin W.Birch S19E 10.13' do
 6" R.Pine N84W 16.93' do
 6" R.Pine N22W 36.09' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/11/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

