

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>16W</u>	<u>L11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													25
12	31			32			33			34			35
13													36

I, Stephan J. Szyszkoski, in a field survey on 06/03/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L11) Quarter corner common to Sections 25 and 36. 1850 - Established by Wm. Ives Deputy Surveyor midway and on the Section line between Section corners 40.11 chains east and west. Set post. Hemlock 10" S46W 26 links, Beech 7" N38E 44 links. 1948 - Remonumented by R.J. Brotherton RLS from Hemlock BT S46W 26 links, found "perfect" and "already chopped out", 40.18 chains west of Section corner M11 and, according to his record for that corner, 40.16 chains east of Section corner K11. Brotherton's record of his measurements from M11 to L11 and thence to K11 indicate that he found a deflection in the Section line at this original corner of 29 minutes right. Mr. Brotherton set 4" post at the corner. 10" Hemlock S66W 19.3', 16" Beech S45E 17.0', GLO Hemlock BT S46W 26 links. GLO Beech BT is missing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L11) The original post and accessories were not recovered. Brotherton's post and accessories were not recovered. Found a slab on the ground of what appears likely to have been Brotherton's Hemlock NBT but did not find enough evidence to determine Brotherton's corner position. Reestablished the corner position proportionate to Brotherton's measurements to corners east and west and at a northing to yield the 29 minute deflection. Thus, bearings and distances to Section corners: S 89 deg. 52'26"W 2648.35' and N 89deg. 23'26"E 2649.67'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L11) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 13" Hemlock N44E 10.14' mrkd "1/4S NBT"
 16" Hemlock S84E 24.51' do
 13" Maple S12E 12.46' do
 7" Maple N74W 21.28' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/10/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities