

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 16W	K11
	T 49N R 16W	M12
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on M12 10/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K11) Corner common to Sections 25-26-35-36. 1850 - Established by Wm. Ives Deputy Surveyor. Set post. Beech 14" S55E 23 links, Beech 6" N46W 40 links. 1948 - R.J. Brotherton RLS remonumented the corner in the original position: "We had to chop out the Govt. Beech BT to verify the same, then set the post in plain old hole in ground under the leaf cover. Remains of the Beech BT in SE position was noted. Set 4" post from Govt. Beech BT in NW position, now 22" dia. No witnesses were made on 4/28/48. Later made the following NBTs: 5" Hemlock N23E 7.1', 9" Hemlock S50E 32.0'."

(M12) Quarter corner common to Section 36 T49N-R16W and Section 31 T49N-R15W. 1841 - Established by Wm. A. Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Y. Pine 20" N54E 26 links, Y. Pine 20" N31W 31 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K11) Found the post hole of Brotherton's post at record distance and approximate bearing from his Hemlock NBTs, both in good condition. Also found leaf spring driven adjacent. The GLO Beech NW noted in the 1948 record was not found. Accepted the post hole and leaf spring as a careful and faithful perpetuation of the position of the original corner and remonumented same.

(M12) The original post was not recovered. Remonumented the corner at record bearing and distance from the rotting stump remains of the two 1841 Y. Pine BTS, iron marks visible. Found leaf spring, not of record, laying on ground surface nearby. The leaf spring was likely placed ca. 1948 by R.J. Brotherton and subsequently disturbed and removed from position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K11) Set 1" IDx36" I. pipe with plastic MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Hemlock N43E 6.99' mrkd "S25" RJB NBT  
 16" Hemlock S44E 32.42' mrkd "S36" do  
 15" Hemlock N72W 21.48' mrkd "S26 NBT"  
 5" Maple S11W 16.99' mrkd "S35 NBT"  
 Bearings are magnetic.

(M12) Set 1" IDx36" I. pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 16" R. Pine S06E 2.0' mrkd "1/4S NBT"  
 14" R. Pine West 10.65' do  
 17" R. Pine N30W 20.47' do  
 8" Maple clump N08E 26.62' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/10/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

