

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Alger	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 36 T 49N R 16W	5
	S 36 T 49N R 16W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/15/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (5-Sec. 36) North 1/16 corner, Section 36. Not established in the original survey.
- (8-Sec. 36) West 1/16 corner, Sec. 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (5-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1315.45' north and Center of Section 1315.45' south.
- (8-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1324.91' west and Center of Section 1324.91' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <ul style="list-style-type: none"> (5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" Maple S13E 17.08' mrkd "N1/16 BT" 14" Maple S40W 34.7' do 7" Maple N55W 14.86' do 13" Maple S35E 29.88' do Bearings are magnetic. | <ul style="list-style-type: none"> (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 9" Hemlock S03E 28.57' mrkd "W1/16 BT" 19" Maple S45E 31.3' do 12" Hemlock S68E 44.25' do 15" Maple N13E 39.33' do Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/10/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities

47245
47246