

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Alger</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 36 T 49N R 16W	7
	S 36 T 49N R 16W	10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

I, Stephan J. Szyszkoski, in a field survey on 7 06/03/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 36) North 1/16 corner between Sec. 36 T49N-R16W and Sec. 31 T49N-R15W. Not established in the original survey.

(10-Sec. 36) South 1/16 corner between Sections 35-36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 36) Established the corner midway and on the Range line between Section corner 1320.08' north and Quarter corner 1320.08' south.

(10-Sec. 36) Established the corner midway and on the Section line between Section corner 1320.08' south and Quarter corner 1320.08' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 11" R.Pine S17W 44.16' mrkd "N1/16 BT"  
 15" R.Pine S82E 57.44' do  
 11" Oak N45E 43.95' do  
 7" W.Pine N48W 50.8' do  
 Bearings are magnetic.

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 7" Maple N52E 9.01' mrkd "S1/16 BT"  
 10" Hemlock N28W 44.95' do  
 16" Hemlock S40E 2.98' do  
 15" Hemlock S35W 22.05' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/10/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities