

Approved by Alger County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 4-8 1995

Geordie Carlson
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

4-275

For corners in

Alger (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>13W</u>	<u>112</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
TIME 9:00 a.m.

APR 20 1995

DONALD W. KINNUNEN
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION**

MAY 10 1995

COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. James, in a field survey on October 21, 1994, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I12: PLS-Francis Coleman, DS, 1851, Set Qr. Section Post- 8.Oak 4", N.61 W., 15 links, W.Pine 10", S.43 E., 19 links. CCI Forestry Division, Land and Timber Examination Report, R.H. Ewalt, 1943 through present, indicates an original GLO W.Pine Bearing Tree at corner location. No other subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I12: Began at existing BT corner monument at the corner of Sections 34 and 35, T.49N., R.13W. Ran corrected compass line on GLO bearing North for a distance of 40.0 chains. Found post and a Red Pine, 18", squared with signatures, S.20 W., (M), 3.0 ft. from post. Found original BT in S.43 E., position, W.Pine 24" with scribing and notch still visible from which existing post measures GLO distance and direction. Replaced existing post with new monument and established references. Corner lies in open area of mixed and scattered timber.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I12: Replaced post with 2 1/4" Alum. Monument w/ 3 1/4" Alum. Cap stamped to I.D. corner position. Established reference trees w/ BT signs, blazed, scribed & painted. Set PK nails for measure w/ brass I.D. washers in the following reference trees. Existing (orig. BT) W.Pine 24", S.43 E., 12.63 feet, "Ex.Blazes", W.Oak 6", N.30 E., 40.33 feet, "1/4s BT", R.Pine 14", S.57 W., 30.20 feet, "1/4s BT", R.Pine 14", N.35 W., 17.21 feet, "1/4s BT", Steel witness post with Survey marker sign, N.71 E., 2.2 feet, All bearings are magnetic.

Signed by

Robert L. James
25849

Date

12 April, 1995

Surveyor's Michigan License No.