

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Alger County
Land Surveyors' Remonumentation
Peer Group Under Act 74 of
P.A. of 1990 On 12/16 1998

Robert L. Jamros
Chairman

05-111

For corners in

Alger <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>50N</u> R <u>13W</u>	K <u>12</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

FILED
TIME 10:00 AM.

JAN 8 1999
DONALD W. KINNUNEN
REGISTER OF DEEDS
ALGER COUNTY, MI

Register of Deeds Stamp & File Number

I, Robert L. Jamros, in a field survey on September 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35	●	36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K12: P.L.S. - Francis Colman, DS, 1851. Set quarter section post. Y. Pine 14, N.49°W., 39 links, Y. Pine 12, S.75°E., 27 links. ***** No other record of restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K12: Located corner position by standard field survey and record measurement. Corner position established at record distance North of section corner to South and on a mean bearing between the West line of Section 35 and the East line of Section 36. GLO evidence of corner position has been destroyed. Monumented corner position and established new reference trees. Position as monumented is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K12: Set Berntsen aluminum monument no. AINB30, stamped to identify corner position. Established the following reference trees with BT signs, blazed, scribed and painted. Set PK nails for measure with aluminum I.D. washers in the following. * Red Pine 10", N.36°W., 15.02 feet, "1/4S BT"; * Red Pine 8", N.66°E., 16.60 feet, "1/4S BT"; * Red Pine 8", S.48°E., 33.43 feet, "1/4S BT"; * Red Pine 8", S.64°W., 4.68 feet, "1/4S BT". * Survey marker sign on 6 foot steel post, N.27°E., 1.0 feet. All bearings are magnetic.

Signed by Robert L. Jamros
Surveyor's Michigan License No. 25849

Date December 16, 1998

