

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 COMMERCIAL

ALLEGAN (County)	Located in:	Corner Code #
1. Public Land Survey	T 1 N R 11 W	A-1 (NW, 6)
	T _____ R _____	Gun Plain
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1993 DEC 30 PM 2:44
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


I, David F. Peabody, in a field survey on October, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. (Stone) Donald Ratekin (County Surveyor) 1973
 Maple 14 NE 49.4' Stone W/Cross
 MSHD (1957) T. Pole N30°W 52.87'
 Stone X, Axe Bit 26" Maple N18°W 44.40'
 23" Maple N18W 43.87' 31" Maple N66°E 50.50'
 16" Walnut S32E 30.24' In line W/ fence to S.
 28" Maple N66E 49.68' P.P. SE 39.60'
 LCRC L.02, P.129

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Stone (Top part had been chipped off)
 Maple 14 NE 49.4'
 26" Maple N18°W 44.40'
 31" Maple N66°E 50.50' (appears to be same from G.L.O.)
 T. Pole N30°W 52.87'
 P.P. SE 39.60'
 This Corner is accepted as a careful and faithful perpetuation of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Removed Stone And Placed 3/4" iron W/Remon Cap
 Nail SW Side T. Pole N40°W 52.87'
 20d Nail W/Allegan Co. Tag SW Side 32" Maple N18°W 43.82'
 20d Nail SW Side Power Pole S37°E 39.38'
 20d Nail W/Allegan Co. Tag W. Side 12" Elm S15°W 23.15'
 3'± E. of Brush line South
 28'± SE of C.L. Gravel Road



Signed by David F. Peabody Date 12/20/93
 Surveyor's Michigan License No. 25866