

# SURVEY & REMONUMENTATION

APR 24 1995

## COMMISSION

### ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

<u>ALLEGAN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 1 N R 11 W	A-13 (SW, 31)
	T _____ R _____	Gun Plain
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
 ALLEGAN COUNTY MICHIGAN  
 1994 JUN -3 PM 1:17  
*James L. Batten*

FILED

Register of Deeds Stamp & File Number

I, David F. Peabody, in a field survey on March 01, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (set post)	Donald A. Ratekin (County Surveyor) 1972
Birch 8 N25W 41	23" Elm N. 22.8'
Sugar 7 N32½E 70	SE Cor of house NW 87.8'
	24" Elm WNW 49.2'
	32" Elm WNW 77.8'
	1" Iron (Boat Spike)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat Spike in Monument Box  
 SE Cor of house NW 87.8'  
 Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

**APPROVED REMONUMENTATION CORNER**  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 4-12-94  
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed Boat Spike and placed 3/4" Iron W/Remon Cap in Monument Box  
 Face 6" Spruce N45°W 34.2'  
 20d nail W/Allegan Co. Tag E. Side P. Pole N. 64.00'  
 20d nail W/Allegan Co. Tag NW Side P. Pole S15°W 105.40'  
 20d nail W/Allegan Co. Tag NE Side T. Pole S60°E 81.11'  
 20d nail W/Allegan Co. Tag N. Side 14" Maple N70°W 90.44'  
 Corner of House N40°W 87.78'



Signed by David F. Peabody Date 5/10/94  
 Surveyor's Michigan License No. 25866

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

LIBER 004 PAGE 379