

MAR 15 1993

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN
County

	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N R <u>11</u> W	<u>B-7 (S$\frac{1}{4}$, 18)</u> <u>Gun Plain</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1993 DEC 30 PM 2:11

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

Register of Deeds Stamp # File Number

FILED

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7	▲												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David F. Peabody, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	Wightman Moored INC. 1993
W. Oak 14 N66W 77	Fd. Monument Box
B. Oak 8 S55E 71	Nail in top of Guard Rail Post S42°W 26.74'
	" " " " " " " S43°E 25.22'
MSHD (1956) Iron pin in Raod	" " " " " " " N40°W 26.16'
49" Elm N50E 39.6'	" " " " " " " N40°E 25.17'
Tele. Pole N05W 27.16'	
25" Burr Oak South 86.60'	
Gas Line Blow Cock SW 36.9'	
Power Pole South 27.8'	


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G.L.O. All Gone
MSHD All Gone
Found Bolt Spike in Mon. Box
Nail in top of Guard Rail Post S42°W 26.74'
" " " " " " " S43°E 25.22'
" " " " " " " N40°W 26.16'
" " " " " " " N40°E 25.17'

This Corner is accepted as a careful and faithful reestablishment of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" iron W/Remon Cap in Monument Box (Replacing Bolt Spike) in C.L. Road
Nail in top of Guard Rail Post S42°W 26.74'
" " " " " " " S43°E 25.22'
" " " " " " " N40°W 26.16'
" " " " " " " N40°E 25.17'



Signed by David F. Peabody Date 12/20/93
Surveyor's Michigan License No. 25866

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982