

# SURVEY & REMONUMENTATION

APR 29 1996

Allegan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners **COMMISSION**

Allegan <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1 N</u> R <u>11 W</u>	<u>C-1 (NW, 5)</u> <u>Gun Plain</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 APR 24 PM 2:20  
*Joyce E. Bates*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
**FILED**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David F. Peabody, in a field survey on November 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (Set Post)	Peabody Land Surveying 1981 survey
W. Oak 7 S57E 26	Fd. 1" Iron
Do. 12 S63W 25	28" Oak S35°W 46.5'
	P. Pole S40°W 79.92'
	P. Pole N45°W 78.66'
	C/L Rd. East 32'±
Austin Williams LCRC (L.3, P.91)	
Fd. 1 1/2" Iron	
PK Nail in Power Pole S40°W 79.95'	
PK Nail in Power Pole N35°W 78.67'	
Center of 3" Steel Sign Post N70°E 105.60'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1" Solid Iron Rod in Mon. Box  
G.L.O. All Gone  
All Austin Williams & Peabody Land Surveying Accessories were located & used  
And is accepted as a careful and faithful perpetuation of the position of the original corner

APPROVED REMONUMENTATION CORNER  
P.A. 343 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-8-94  
COUNTY REP. *David F. Peabody*

Peer Group Approved 11-08-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" Iron W/Remon Cap on Township Line  
Found 1" Solid Iron (closing corner) North 0.15'  
Fd. PK Nail NE Side P. Pole N40°W 78.64'  
Fd. PK Nail E. Side P. Pole S40°W 79.92'  
20d Nail W/Allegan Co. Tag W. Side 30" Oak S35°W 47.80'  
SW Cor. MBT Box N15°E 80.2'  
SW Cor. Sec. 32 (Martin Twp.) C-13 East 149.90'  
C/L Rd. North 5'±



REF 0005 PAGE 174

Signed by David F. Peabody Date 1/26/95  
Surveyor's Michigan License No. 25866