

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in

ALLEGAN (County)
 Located in: Corner Code #
 1. Public Land Survey T 1 N R 11 W C-7 (SE, 18)
 T R Gun Plain
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____


1993 DEC 30 PM 2:11
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 Register of Deeds Stamp & File Number
 FILED

I, David F. Peabody, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules heretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	3	4	5	6	7	8	9	10	11	12	13	14
3	4	5	6	7	8	9	10	11	12	13	14	15
4	5	6	7	8	9	10	11	12	13	14	15	16
5	6	7	8	9	10	11	12	13	14	15	16	17
6	7	8	9	10	11	12	13	14	15	16	17	18
7	8	9	10	11	12	13	14	15	16	17	18	19
8	9	10	11	12	13	14	15	16	17	18	19	20
9	10	11	12	13	14	15	16	17	18	19	20	21
10	11	12	13	14	15	16	17	18	19	20	21	22
11	12	13	14	15	16	17	18	19	20	21	22	23
12	13	14	15	16	17	18	19	20	21	22	23	24
13	14	15	16	17	18	19	20	21	22	23	24	25

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. (Set Post) Consumers Power Company 1960's ±
 B. Oak 10 N68W 26 Found Monument Box
 Do. 12 N87E 36
 Resurvey (County Surveyor) 1908 Donald Ratekin (County Surveyor) 1974
 Maple 10" NW 54.5' Found 1" iron in Mon. Box
 Oak 10" NW 69 NW Cor. Store S45°E 80.98'
 Stake CL Gas Marker N60°E 55.89'
 Nail in P.P N45°E 55.92'
 LCRC L.02 P.325
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1" iron in Monument Box
 NW Cor. Store S45°E 80.98'
 CL Gas Line Marker N60°E 59.47'
 This Corner is accepted as a careful and faithful reestablishment of the position of the Original Corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Put Remon Cap over iron in Monument Box
 NW Cor. Store S45°E 80.98'
 CL Gas Line Marker N60°E 59.47'
 P.K. Nail NW'LY Side Power Pole S45°W 95.68'
 P.K. Nail N'LY Side Power Pole N60°W 55.80'
 P.K. Nail S. Side Power Pole N75°E 168.20'
 P.K. Nail W. Side 36" Elm S37°E 126.80'



Signed by David F. Peabody Date 12/20/93
 Surveyor's Michigan License No. 25866

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983