

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1</u> N R <u>11</u> W	<u>E-1 (NE, 5)</u> <u>Gun Plain</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 APR 24 PM 2:20
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James H. Decker

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	25	26	27	28	25							
11													
12	31	32	33	34	35	36							
13													

I, David F. Peabody, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. (Post set) Ratekin survey 1983±
 W. Oak 10 S45E 31 PK Nail in P. Pole SW 104.14'
 Do. 9 S31W 34 PK Nail in P. Pole NE 83.51'
 PK Nail in 10" Oak SW 48.18'
 PK Nail in 16" Oak ESE 89.21'
 PK Nail in R.R. Tie Post SSW 62.59'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FD. Capped Rerod (R.E.M.)
 G.L.O. All Gone
 PK Nail in P. Pole SW 104.14'
 PK Nail in P. Pole NE 83.51'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-8-94
 COUNTY REP. *Rick A. [Signature]*

Peer Group Approved 11-08-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 3/4" Iron W/Remon Cap on Township Line
 Found capped rerod (closing corner) North 0.65'
 20d Nail W/Allegan Co. Tag NW Side 18" Oak S55°W 47.70'
 Fd. PK Nail in NE Face P. Pole S50°W 103.85'
 Fd. PK Nail in NW Face P. Pole N45°E 83.95'
 20d Nail W/Allegan Co. Tag S. Side 28" Oak S70°E 90.00'
 SE Cor. Sec. 32 (Martin Twp.) E-13 East 146.81'
 in C/L Rd. E & W



LIFE # 0005 PAGE 173

Signed by David F. Peabody Date 1/26/95
 Surveyor's Michigan License No. 25866