

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>11W</u>	* <u>M-1 (NE, 1)</u> GUN PLAIN TWP
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>M-13 (SE, 36)</u> MARTIN TWP
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

1995 DEC 14 PM 2:33
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 J. J. ...
 REGISTER OF DEEDS STAMP & FILE NUMBER

**SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ADDRESS in a field survey on 14 OCT, 19 95
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O.
 SET TWP COR 40 LKS S OF TEMP. POST
 W. OAK 9 44 1/2° W 29
 B. OAK 12 S 65° E 17

CONT. ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FD 2" TILE W/ ROCKS AROUND IT.
 TWIN OAK W 41.0'±
 16" OAK S 10° E 9.5'±
 DIST S TO M-2 2673.75'
 DIST W TO L-1 2641.01'
 SET STD. ALLEGAN CO. MON. IN CENTER OF TILE
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE
 POSITION OF THE ORIGINAL MONUMENT.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 9-12-95
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 STD. ALLEGAN CO. MON. (3/4" X 24" IRON W/ CAP) IN 2" TILE W/ STONES
 AROUND IT.
 16d REMON TAG W. SDE 16" OAK S 10° E 9.53'
 16d REMON TAG NE. SDE 12" OAK S 55° E 25.29'
 16d REMON TAG S SDE 14" OAK N 85° E 27.70'
 16d REMON TAG W SDE 22" MAPLE N 15° E 47.44'
 16d REMON TAG N SDE 10" MAPLE N 75° W 41.92'
 16d REMON TAG NW SDE 6" MAPLE S 60° W 30.54'
 IN LINE W/ OLD DOWN FE TO EAST



Signed by [Signature] Date 4 DEC 95
 Surveyor's Michigan License No. 30075

A. DESCRIPTION OF . . . SUBSEQUENT RESTORATION

CESSY, BARRY CO. SURVEYOR 1884
FD OLD BEARINGS & POST SET TILE
W. OAK 12 N 41 $\frac{1}{2}$ ° W 19 $\frac{1}{2}$ '
W. OAK 14 N 22° E 17'

OLD ALLEGAN COUNTY SURVEYORS' NOTES
2" TILE W/ ROCKS AROUND IT.
TWIN OAK W 41.0'
12" SOFT MAPLE NW 16.2'

D.A. RATERIN, C.S. 1971
DIST S TO M-2 2623.82
DIST W TO L-1 2642.29

L.C.R.C. L-1, P- 193 4-18-72
2" TILE W/ ROCKS AROUND IT
30" MAPLE N 50° W 15.6'
40" TWIN OAK W 41.0'
20" MAPLE S 15° E 9.4'