

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T- <u>1N</u> R- <u>11W</u>	<u>M-2 E1, 1</u> <u>GUN PLAIN TWP</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

97 JAN 22 PM 1:23  
REGISTER OF DEEDS  
ALLEGAN COUNTY  
*Register of Deeds Stamp & File Number*

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BASIL ADDRESS, in a field survey on FEBRUARY 10, 19 96  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O.  
40 SET QR. SEC. POST NOV. 28, 1868 J.W. HICKS, C.S.  
W. OAK 9 S 14° W 80 SHOWS COR.  
Y. OAK 8 N 82½° W 23 AUG. 7, 1876 J.W. HICKS, C.S.  
SURVEYED SE ¼  
OLD COUNTY SURVEYOR'S NOTES  
SHOW IRON & STONE  
DIST SOUTH 2692.1 TO M-3

**CONTINUED ON BACK OF CERTIFICATE**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Fd 1" PIPE & STONE @ INT. OF N-S-W FENCES (DOWN)  
24" CHERRY N 15° E 29.7'±  
30" OAK SOUTH 14.7'±  
24" HICKORY NORTH 26.3'±  
DIST N 2623.75' TO M-1  
DIST S 2689.78' TO PROP. CONT. COR. (PREV. USED AS M-3)  
REPLACED W/ STD. ALLEGAN CO. MON. 3/4" X 36" STEEL PIN W/ CAP  
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION  
OF THE POSITION OF THE ORIGINAL MONUMENT.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 9-13-96  
COUNTY REP. Basil J. Address

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. ALLEGAN CO. MON.  
A-2 (STD. BARRY CO. MON.) T-1N, R-10W SOUTH 21.12'  
16d & REMON TAG S.E. SDE 14" BEECH N 80° E 23.97'  
16d & REMON TAG N.E. SDE 8" HICKORY S 45° E 23.16'  
16d & REMON TAG E. SDE 30" OAK SOUTH 15.81'  
16d & REMON TAG S.E. SDE 18" ASH S 20° W 45.13'  
IRON W/ CAP SOUTH 34.10'  
AT INT. OF OLD DOWN FE TO N-S-W  
STEEL FE POST SSW 0.4'



Signed by Basil J. Address Date 13 FEB 96  
Surveyor's Michigan License No. 30078

18820605 PAGE 388

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

CONTINUED FROM FRONT OF CERTIFICATE

A. DESCRIPTION OF ORIGINAL . . . SUBSEQUENT RESTORATION

JULY 6, 1971 D.A. RATEKIN, C.S.

REC'D SURVEY L-794, P-55

SECTION BREAKDOWN ON WITNESS CARD SHOWS:

DIST SOUTH 2690.10' TO M-3

DIST NORTH 2623.82' TO M-1

APR. 4, 1972 D.A. RATEKIN, C.S.

L.C.R.C. L-1, P-190

1" IRON PIPE & STONE

15" CHERRY N 15° E 32.0'

20" OAK SOUTH 5.2' (SHOULD BE 15.2')

24" ASH NORTH 26.6'

IN N & S FENCE

APR. 22, 1982 D.F. PEABODY, P.S.

USED IN A SURVEY

SHOWS DIST SOUTH 1345.05' TO 1/8 LINE

DEC. 15, 1986 R.E. MOORED, P.S.

USED IN A SURVEY

SHOWS DIST SOUTH 34.10' TO A SET IRON ON SEC. LINE

