

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

*Spencer M. Anderson*  
 REGISTERED PROFESSIONAL SURVEYOR  
 ALLEGAN COUNTY, MICHIGAN

1995 DEC 14, PM 2:33

FILED

SURVEY &  
 REMONUMENTATION  
 APR 29 1996  
 COMMISSION

For corners in

| ALLEGAN<br>(County)                   | Located In:              | Corner Code                                 |
|---------------------------------------|--------------------------|---|
| 1. Public Land Survey                 | T <u>1N</u> R <u>11W</u> | <u>M-5 (SE, 12)</u><br><u>GUN PLAIN TWP</u> |
|                                       | T _____ R _____          | _____                                       |
|                                       | T _____ R _____          | _____                                       |
|                                       | T _____ R _____          | _____                                       |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____                                       |
|                                       | S _____ T _____ R _____  | _____                                       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____                                       |
|                                       | S _____ T _____ R _____  | _____                                       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, BASIL ADDRESS in a field survey on 2 DEC, 19 95  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as  
 expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O.  
 80.00 SET POST COR SECTIONS 12 & 13  
 W. OAK 9 S 38° W 18  
 Y. OAK 17 N 73½° W 23

CONT. ON BACK

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FD R.R. SPK IN MON BOX  
 1 1/4' PIPE (A-5, T-1N, R-10W) NORTH 21.12'  
 22" HICKORY N 35° E 60.6'±  
 IN C/L DOSTER RD ±  
 REPLACED R.R. SPK W/ STD. ALLEGAN CO. MON. (3/4" X 24" IRON W/ GAP)  
 AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE  
 ORIGINAL MONUMENT.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990

ALLLEGAN COUNTY  
 DATE APPROVED 11-14-95  
 COUNTY REP. Paul L. Van Doren

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 STD. ALLEGAN CO. MONUMENT (3/4" X 24" IRON W/ GAP) IN MON. BOX  
 A-5 (T-1N, R-10W) (STD BARRY CO. MON.) NORTH 21.12'  
 16d REMON TAG E SDE 36" OAK S 25° W 61.80'  
 16d REMON TAG SW SDE P.P. S 20° E 79.58'  
 16d REMON TAG SE SDE 22" HICKORY N 35° E 61.70'  
 16d REMON TAG E SDE 32" OAK N 10° W 177.92'  
 IN C/L DOSTER RD ±  
 C/L 108TH AVE TO WEST IS SOUTH 5'±



Signed by Basil J. Anderson, Jr.  
 Surveyor's Michigan License No. 30075

Date 4 DEC 95

## A. DESCRIPTION OF . . . SUBSEQUENT RESTORATION.

J.W. HICKS, C.S. CIRCA: 1880'S  
STONE  
DIST N TO M-4 40.23'  
DIST W TO L-5 40.47'

D.F. PEABODY, P.S.  
L.C.R.C. L-003, P-318 7-27-81  
FD P.K. NAIL  
3/4" PIPE (A-4, T-1N, R-10W) NORTH 21.12'  
C/L RD EAST 1'  
NW COR TEL PED S 60° E 44.1'  
14" HICKORY N 35° E 60.6'

R.E. MOORED, P.S.  
FD R.R. SPK 11-14-89  
1 1/2" PIPE N 21.12'

D.R. PITTS, P.S.  
SURVEY 2-9-94  
DIST W TO L-5 2668.22'