

ALLEGAN COUNTY REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Joyce A. Little*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

98 JAN 21 PM 1:23

FILED

SECTION Located In: Corner Code #

For Corners in ALLEGAN (county)

1. Public Land Survey T 1N R 11W M-6  
EAST 1/4 CORNER T \_\_\_\_\_ R \_\_\_\_\_  
SECTION 13 T \_\_\_\_\_ R \_\_\_\_\_  
GUN PLAIN TOWNSHIP T \_\_\_\_\_ R \_\_\_\_\_  
ON RANGE LINE

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 24 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1825 (R11W, P.10) "40.00 SET POST 1/4 SECTION CORNER" Y OAK 17 N38W 23 W OAK 9 S69W 14
- NO MENTION OF THIS CORNER WAS FOUND IN THE RECORDS OF THE BARRY OR ALLEGAN COUNTY SURVEYOR.

\*\*\* NO HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. CORNER LIES IN A 6'-7' FILL AREA. FOUND A-6, T1N, R10W. SET CORNER AT MID POINT BETWEEN M-5 AND M-7, AND ON LINE BETWEEN M-7 AND A-6 (T1N, R10W). ACCEPTED AS BEST EVIDENCE OF CORNER POSITION.


SET STANDARD ALLEGAN COUNTY REMONUMENTATION MONUMENT.

Peer group approved Aug. 12, 1997.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 8-12-97  
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH PLASTIC CAP  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N15°E 53.49'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N14°W 53.26'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S35°E 23.10'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S36°W 23.66'  
CORNER LIES ON CENTERLINE NORTH-SOUTH BITUMINOUS ROAD (DOSTER ROAD)  
A-6 T1N, R10W LIES NORTH 31.62'



Signed by *Brian Reynolds*  
Surveyor's Michigan License No 31602

Date 8-13-97

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975 REVISED JANUARY, 1983 REVISED OCTOBER 1995