

**SURVEY & REMONUMENTATION ALLEGAN COUNTY REMONUMENTATION**

**APR 07 1998** LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in **SECTION** Located In: Corner Code #  
ALLEGAN  
(county)

1. Public Land Survey T 1N R 11W M-8  
EAST 1/4 CORNER T R  
SECTION 24 T R  
GUN PLAIN TOWNSHIP T R  
ON RANGE LINE
2. Property Controlling S T R  
in Section S T R
3. Miscellaneous S T R  
Property in Sec. S T R
4. Lot No \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

98 JAN 21 PM 1:23  
*Joyce A. ...*  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 24 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1825 (R11W, P.10) "40.00 SET POST 1/4 SECTION CORNER" W. ASH S49W 36 W. OAK N75 1/2W 67
- NO MENTION OF THIS CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYORS RECORDS.
- ACT 132 SURVEY: BY DENNIS A. MIDDLETON, P.S. #16049, 8-21-72, (L.1,P.51, BARRY COUNTY RECORDS) CORNER WAS NOT WITNESSED, BUT IS REFERENCED AS 2668.86' NORTH OF M-9, T1N, R10W.
- ACT 132 SURVEY: BY DENNIS A. MIDDLETON, P.S. #16049, 12-6-72, (L.1,P.62, BARRY COUNTY RECORDS) CORNER WAS NOT WITNESSES, BUT IS REFERENCED AS 23.71' SOUTH OF A-8, T1N, R10W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND NO MAGNETIC EVIDENCE OF CORNER MONUMENTATION. CORNER LIES IN A 15'+ FILL AREA. FOUND A-8, T1N, R10W (5/8" IRON IN MONUMENT BOX) AND MEASURED 2692.57' BETWEEN A-8 & M-9 (FOUND 2" PIPE FILLED WITH CONCRETE IN DOSTER LAKE). SET M-8 ON LINE PROJECTED FROM M-7 THROUGH A-8, 23.71' SOUTH OF A-8. DISTANCE FROM REESTABLISHED M-8 TO FOUND M-9 MEASURES 2668.86 FEET, CONFORMING EXACTLY WITH MIDDLETON'S DISTANCES NORTH AND SOUTH (ITEMS #3 & #4 ABOVE). ACCEPTED AS PROPER RESTORATION OF CORNER POSITION REFERENCED BY MIDDLETON. SET STANDARD ALLEGAN COUNTY REMONUMENTATION MONUMENT.

Peer group approved Aug. 12, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH PLASTIC CAP CORNER LIES 1.5'+/- WEST OF CENTERLINE OF NORTH-SOUTH BITUMINOUS ROAD (DOSTER ROAD)  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N20°W 37.17'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N25°E 38.55'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S58°E 18.73'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S60°W 16.27'  
A-8, T1N, R10W, LIES N00°07'43"E 23.71'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 8-12-97  
COUNTY REP. K.V.O.



Signed by *Brian Reynolds*  
Surveyor's Michigan License No 31602

Date 8-13-97

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975 REVISED JANUARY, 1983 REVISED OCTOBER 1996