

APR 07 1998 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in **SECTION** Located In: Corner Code #
ALLEGAN
(county)

1. Public Land Survey T 1N R 11W ✓ M-9
CORNER COMMON TO T _____ R _____
SECTIONS 24 & 25 T _____ R _____
GUN PLAIN TOWNSHIP T _____ R _____
ON RANGE LINE
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No _____, Recorded Plat _____
5. Private Claims _____

98 JAN 21 PM 1:23
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
FILED

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 10 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1825 (R11W, P.10) "80.00 SET POST CORNER TO SECTIONS 24 & 25" TAMARACK 6 N18 1/2W 26 Do. 6 S23 1/2W 27
- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R10W, P.32 FOR A-9, T1N, R10W, BARRY COUNTY RECORDS) "WEST 82.39 INTERSECTED W. BOUNDARY 46 N. OF POST" A TAMARACK 7 N21W 33 A. B. ASH 8 S35E 44
- NO MENTION OF THIS CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYOR RECORDS.
- RECORDED PLAT OF "SHANGRI-LA NUMBER TWO" AS RECORDED IN (BARRY COUNTY RECORDS) LIBER 5 OF PLATS, ON PAGES 71-73, SEPTEMBER 26, 1969, CORNER WAS NOT WITNESSED, BUT REFERENCED AS BEING 30.36' SOUTH OF A-9, T1N, R10W
- ACT 132 SURVEY: BY DENNIS A. MIDDLETON, P.S. #16049, 9-20-72, (BARRY COUNTY RECORDS) L.1, P.51, CORNER WAS NOT WITNESSED, BUT REFERENCED AS BEING 30.36' SOUTH OF A-9, T1N, R10W.
- ACT 132 SURVEY: BY DENNIS A. MIDDLETON, P.S. #16049, 12-6-72, (BARRY COUNTY RECORDS) L.1, P.62, CORNER WAS NOT WITNESSED, BUT REFERENCED AS BEING 30.36' SOUTH OF A-9, T1N, R10W.
- ACT 132 SURVEY: BY WENLEY Q. SMITH, P.S. #8528, 3-18-76 (L.884, P.581), REFERENCED AS "30.36' SOUTH OF THE S.W. CORNER SEC. 19, T1N, R10W" NO WITNESSES GIVEN.
- BARRY COUNTY ROAD COMM. WITNESS CARD: NO NAME OR DATE, "2"IRON" 26" OAK NE 65.4' 18" WHITE WOOD WNW 79.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 2" PIPE FILLED WITH CONCRETE, 8"+ BELOW THE SURFACE OF DOSTER LAKE. FOUND NO WITNESSES FROM THE ROAD COMM. (ITEM #8). MEASURED TO A-9, T1N, R10W, WHICH IS A PLAT MONUMENT AND ANOTHER PLAT MONUMENT 17' FURTHER NORTH (SHOWN ON THE PLAT OF SHANGRI-LA NO. 2, ITEM #4). DISTANCES TO BOTH FOUND PLAT MONUMENTS CONFIRM POSITION AS RECITED IN ITEMS #4, #5, #6, & #7.
ACCEPTED FOUND 2" PIPE FILLED WITH CONCRETE AS BEST EVIDENCE OF CORNER POSITION.
WE WERE UNABLE TO REMOVE FOUND PIPE. LEFT FOUND 2" PIPE FILLED WITH CONCRETE IN PLACE.

Peer group approved Aug. 12, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2" PIPE FILLED WITH CONCRETE, 8"+ BELOW THE SURFACE OF DOSTER LAKE (2"+/- ABOVE MUCK).
A-9, T1N, R10W (4" ROUND CONCRETE PLAT MONUMENT WITH 1/2" IRON IN CENTER) LIES N00°14'14"E 30.33'
FOUND "PK" IN THE SOUTH SIDE OF AN 18" WILLOW N31°W 38.26'
FOUND "PK" IN THE WEST SIDE OF A 4" ASH N10°W 40.44'
FOUND "PK" IN THE NORTH SIDE OF A 12" ASH N64°E 52.00'
CONCRETE PLAT MONUMENT LIES N00°33'53"W 48.15'
LAKE SHORE NORTH 12'+/-
LAKE SHORE EAST 10'+/-

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 8-12-97
COUNTY REP. K.V.O.



Signed by [Signature]
Surveyor's Michigan License No 31602

Date 8-13-97