

APR 03 1999

ALLEGAN COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in ALLEGAN Located in: _____ Corner Code # _____
(county)

1. Public Land Survey T 1N R 11W M-11
CORNER COMMON TO _____
SECTIONS 25 & 36 T _____ R _____
GUN PLAIN TOWNSHIP T _____ R _____
ON RANGE LINE

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

98 JAN 21 PM 1:23
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 [Signature]

FILED

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 24 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: JOHN MULLETT, D.S., 1825 (R11W, P. 9) "80.00 SET POST CORNER TO SECTIONS 25 & 36" W. OAK 10 N56W 14 Do. 7 N36W 54
- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R10W, P. 31 FOR A-11, T1N, R10W, BARRY COUNTY) "WEST 81.29 INTERSECTED W. BOUNDARY 62 N. OF POST" A W. OAK 26 S40E 90 A.B. OAK 28 N21E 75
- NO MENTION OF THIS CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYOR RECORDS.
- ALLEGAN COUNTY ROAD COMM. WITNESS CARD: NO NAME OR DATE, "IRON BAR" 12" OAK 35.57 10" HICKORY 59.90 8" ELM 31.02
- ALLEGAN COUNTY ROAD COMM. WITNESS CARD: NO NAME OR DATE, "IRON BAR" 26" OAK NE 34.5' TEL. CABLE MARKER ENE 36.2' FENCE POST W. 32.0' P. P. SE 43.1' 24" HICK 44.9'
- LAND CORNER RECORDATION CERTIFICATE: BY DONALD A. RATEKIN, P.S. #8781 (L.2, P.19), 9-18-72, "FOUND IRON BAR" 26" OAK N45°E 34.5' TEL. CABLE MARKER N67°E 36.2' FENCE POST WEST 32.0' P. POLE S45°E 43.1' 24" HICKORY 44.9'
- SURVEY BY DONALD R. PITTS, Jr., P.S. #25887, 2-14-95, JOB #95-042, REFERENCED, NO WITNESSES GIVEN.

B: Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SOLID IRON SET IN CONCRETE INSIDE MONUMENT BOX. ALL WITNESSES IN PART "A" HAVE BEEN RELOCATED OR DESTROYED.
 ACCEPTED FOUND 1" SOLID IRON IN CONCRETE INSIDE MONUMENT BOX AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.

Peer group approved Aug. 12, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" SOLID IRON IN CONCRETE, IN MONUMENT BOX.
 FOUND NAIL IN THE NORTHWEST SIDE OF A 28" OAK N63°E 41.38'
 SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A UTILITY POLE S47°E 41.79'
 SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 20" HICKORY S43°W 34.14'
 SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 12" TWIN HICKORY N27°E 67.35'
 CORNER LIES 0.5' EAST OF THE NORTH-SOUTH CENTERLINE OF BITUMINOUS ROAD (DOSTER ROAD)
 A-11 T1N, R10W, LIES NORTH 39.00'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-12-97
 COUNTY REP. K.V.O.



Signed by [Signature]
 Surveyor's Michigan License No 31602

Date 8-13-97