

ALLEGAN CO. REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
(County)

Located in:

Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|--------------------|
| 1. Public Land Survey | T <u>WN</u> | R <u>11W</u> | <u>M-13, SE 36</u> |
| | T | R | <u>GUN PLAIN</u> |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

97 JAN 22 PM 1:23
REGISTERED
ALLEGAN COUNTY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, BASIL ADDRESS, in a field survey on MAY 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5										
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|------------------------------|----------------------------------|
| G.L.O. | SEPT. 1, 1972 D.A. RATEKIN, C.S. |
| W. OAK 9 N 71 E 69 | ACT - 132 SURVEY L-1, P-66 |
| W. OAK 10 N 24 W 27 | 1" IRON |
| OCT. 9, 1884 J. CRESSY, D.S. | 1.8' N OF E-W FE |
| FD. OLD COR | IN N-S FE |
| SET TILE | 4-12" OAKS N 03° W 52.3 |
| W. OAK 22 N 88½ E 59 | TWIN 14" OAK N 69.75 |
| | 14" S. HICKORY EAST 59.5' |

CONT. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD BARRY CO. MON. PER PEABODY'S L.C.R.C.
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION
OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 5-14-96
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- BARRY CO. MONUMENT IN CEN. 3" TILE
2'± N OF E-W FE
IN LINE W/ FE TO N
20d SPK & BARRY CO. TAG E. SDE 10" HICKORY S 10° E 24.55'
20d SPK & BARRY CO. TAG SE SDE 16" OAK N 40° E 33.10'
20d SPK & BARRY CO. TAG W. SDE 16" OAK N 10° W 42.44'
20d SPK & BARRY CO. TAG N. SDE 18" OAK N 70° E 62.24'



Signed by [Signature]
Surveyor's Michigan License No. 30075

Date 10 JUN 96

USE 0005 PAGE 390

A. JUNE 2, 1993 J. KORR, JR., P.S.
L.C.R.C. L-004, P-219
THESE WITNESSES APPEAR TO BE TO ANOTHER CORNER

NOV. 8, 1993 D. PEABODY. P.S.
BARRY CO. L.C.R.C. 002095
FD 3/4" IRON IN 3" TILE
275'± W OF N 1/2 COR SEC-1, T-1S, R-11W
1320'± E OF 1ST ST
REPLACED 3/4" IRON W/ BARRY CO. MONUMENT IN 3" TILE
2'± N OF E-W FE
20d SPK W/ BARRY CO. TAG E. SDE 7" HICKORY S 12° E 24.55'
20d SPK W/ BARRY CO. TAG SE SDE 15" OAK N 42° E 33.10'
20d SPK W/ BARRY CO. TAG E. SDE 15" OAK N 09° W 42.44'
20d SPK W/ BARRY CO. TAG NW SDE 18" OAK N 70° E 62.24'