

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>-1N</u> R <u>-12W</u>	<u>B-1 N1/4-6</u>
	T _____ R _____	<u>OTSEGO TWP.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds
 ALLEGAN COUNTY, MICHIGAN
Sagee A. Collette

1994 AUG 16 AM 11:39

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, BASIL ADDRESS, in a field survey on 6 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET BY G.L.O.	1973-D. A. RATEKIN, C.S.
COUNTY SURVEYORS' OLD NOTES	L.C.R.C. L-2, P-149
STAKE & STONE	SET 1" IRON ON PROPORTION DIST. OF N. LINE
DIST. E TO SEC COR 2636.2'	8" OAK SOUTH 69.6'
DIST. S TO 1/8 POST 21.26	FE COR POST SOUTH 20.3'
CONT. S TO CENTER 20.16	NAIL IN FACE OF PP S25E 25.60'
	NAIL IN W SDE 13" ASH S75E 96.74'
	S 1/4 COR SEC-31, T-2N, R-12W, EAST 82.71'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1" IRON PER L.C.R.C. ON LINE BETWEEN COMMON TOWNSHIP CORNER TO WEST AND S 1/4 COR SEC-31, T-2N, R-12W.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" IRON W/ STD. ALLEGAN CO. MON.
 16d W/ REMON. TAG E SDE PP S10E 297.78'
 16d W/ REMON. TAG NW SDE 24" OAK SOUTH 69.30'
 16d W/ REMON. TAG W SDE PP N10E 191.15'
 16d W/ REMON. TAG W SDE 14" MAPLE N60E 114.37'
 STD. ALLEGAN CO. MON. (S 1/4 SEC-31, T-2N, R-12W) EAST 82.87'



Signed by [Signature] Date 24 JUN 94
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1982