

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION
For corners in

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ALLEGAN (County) Located In: Corner Code #

1. Public Land Survey T -1N R -12W C-1 NE-6
T R OTSEGO TWP.
T R
T R

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

REGISTERED CORNERS
ALLEGAN COUNTY
1994 AUG 16 AM 11:39
FILED
James A. Collette

Register of Deeds Stamp & File Number

I, BASTIL ADDRESS, in a field survey on 7 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	1	1	1	3	2	1					
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. NORTH BETWEEN SECTIONS 5 & 6
80.75 INTERSECT N BOUNDARY 125 LKS
W OF COR SET & POST COR SECS 5 & 6
BEECH 18 S22E 18
MAPLE 14 S60W 28
COUNTY SURVEYORS' OLD NOTES
IRON

D. A. RATEKIN, C.S.
WITNESS CARD
IRON
ST. SIGN NE 45.7'
FENCE POST SW 42.9'
SE COR SEC-31 EAST 83.08
L.C.R.C. L-2, P-21

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 3-9-94
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

COULDN'T LOCATE IRON. SET STD. ALLEGAN CO. MONUMENT ON TOWNSHIP LINE AT JOG DISTANCE CALLED OUT ON WITNESS CARD FROM D. A. RATEKIN, C.S. THERE WERE NO WITNESSES REMAINING FROM THE WITNESS CARD OR L.C.R.C. MENTIONED IN SECTION A.

THIS POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. ALLEGAN CO. MON.
16d W/ REMON. TAG NW SDE 4" POPLAR N60E 142.22'
16d W/ REMON. TAG .SW.SDE 6" ELM S80E 96.82'
W. EDGE STOP SIGN POST S25E 46.98'
16d W/ REMON. TAG .NW.COR.RR TIE FE.POST .S50W 42.95'
16d W/ REMON. TAG S SDE 18" POPLAR N65W 68.67'
W. EDGE W LEG OF SIGN N10W 20.66'
STD. ALLEGAN CO. MON. (SE COR SEC-31, T-2N, R-12W) EAST 83.08'
WEST EDGE ST. SIGN POST N45E 34.86'



Signed by [Signature] Date 24 JUN 94
Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983