

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

FOR CORNERS IN: ALLEGAN COUNTY  
LOCATED IN: T. 1N R. 12W CORNER CODE # C-13

1. Public Land Survey SECTION COR. COMMON TO SECTION'S 31 & 32 OTSEGO TOWNSHIP  
T. .... R. ....  
T. .... R. ....  
T. .... R. ....

2. Property Controlling in section S. .... T. .... R. ....  
S. .... T. .... R. ....

3. Miscellaneous Property in Sec. S. .... T. .... R. ....

4. Lot No. .... Recorded Plat .....

5. Private Claims .....

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP & FILE NUMBER

1100007100012

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.  
80.00 SET POST COR SECS 31 & 32  
BEECH 14 N82-1/2E 48  
BEECH 7 N18-1/2W 39  
WEST FROM C-13, 23.64 CHS (1560.24') TO TEMP COR T.1S., R.12 & 13W.
- E. STRONG (KALAMAZOO COUNTY SURVEYOR, NOV. 10, 1875)  
FD. ALLEGAN 1/4 CORNER AND MADE THE JOG THE SAME AS I FOUND IT AT THE NE CORNER BY ACTUAL MEASURE.  
(JOG MEASURES 1.30 CHAINS = 85.80')

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 8, 1998  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION.  
SET CORNER ON LINE BETWEEN D-13 AND A-1 OF ALAMO AT JOG DISTANCE (85.80) MEASURED BY E. STRONG IN 1875. (#2 ABOVE)

SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.  
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 08, 1998  
TOTAL ON ROAD TRAVERSING = 3703.25' TOTAL OFF ROAD TRAVERSING = 1635.95'

B-13 TO C-13 = N 87°-56'-49" E 2816.96' C-13 TO D-13 = N 87°-56'-49" E 2830.39'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL & TAG IN S SIDE 16" OAK N25°W 10.24'  
-NAIL & TAG IN N SIDE 26" MAPLE N70°W 38.84'  
-NAIL & TAG IN SE SIDE 26" BEECH N10°W 51.15'  
-NAIL & TAG IN N SIDE 16" TW OAK S60°E 36.85'  
-B-1 OF T.1S., R.12W. N 87°56'49" E 85.80'

*Raymond Moored* Date 12/16/98

Surveyors License No. 26463

