

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

13007 PAGE 13

<b>FOR CORNERS IN:</b> ALLEGAN COUNTY	<b>LOCATED IN:</b>	<b>CORNER CODE #</b>
1. Public Land Survey	T. 1N R. 12W	D-13
S 1/4 CORNER COMMON TO SECTION 32	T..... R.....	.....
OTSEGO TOWNSHIP	T..... R.....	.....
	T..... R.....	.....
2. Property Controlling in section	S.....T.....R.....	.....
	S.....T.....R.....	.....
3. Miscellaneous Property in Sec.	S.....T.....R.....	.....
4. Lot No. ...., Recorded Plat.....		
5. Private Claims.....		

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY - MICH  
**REGISTER OF DEEDS STAMP & FILE NUMBER**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	-5	4	-3	2	-1							
3													
4	7	-8	9	-10	11	-12							
5													
6	18	-17	16	-15	14	-13							
7													
8	19	-20	21	-22	23	-24							
9													
10	38	-28	28	-27	26	-25							
11													
12	31	-32	33	-34	35	-36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- G.L.O. 40.00 BEECH 24 FOR QR SEC POST
- D. RATEKIN, SURVEY DATED: 09-26-74, REC. L. 899, P. 383  
(RATEKIN RECORDED SAME INFORMATION ON LCRC, L 2, P. 408, DATED: 09-26-74)  
1 1/4" SQUARE IRON  
-7" OAK S85°E 6.68'  
-16" CHERRY NORTH 43.65'  
-18" BIT, HICKORY WEST 17.6'
- WIGHTMAN MOORED INC., SECTION CARD  
1 1/4" SQUARE IRON 1974  
-7" OAK S85°E 6.68'  
-16" CHERRY NORTH 43.65'  
-18" BIT. HICKORY WEST 17.6'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV. 24, 1998  
COUNTY REP. [Signature]

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1 1/4" SQUARE IRON PER NUMBER 2 - 4 ABOVE.  
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON NOV. 24, 1998.  
TOTAL OFF ROAD TRAVERSING = 2608.95'  
BEARING & DIST. FROM D-13 TO E-13 = N 88°-52'-46" E 2608.93'  
BEARING & DIST. FROM D-13 TO C-13 = N 87°-56'-49" E 2630.39'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL & TAG IN W SIDE 20" OAK N40°W 6.48'  
-NAIL & TAG IN E SIDE 18" TW MAPLE S85°W 18.85'  
-NAIL & TAG IN NE SIDE 24" OAK S85°E 18.12'  
-NAIL & TAG IN S SIDE 20" CHERRY NORTH 44.8'  
-IN EAST & WEST FENCE LINE

[Signature] Date 12/16/98  
Surveyors License No. 26463

