

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 1N R. 12W	E-13
SECTION COR. COMMON TO SECTION'S 32 & 33 OTSEGO TOWNSHIP	T. R.
	T. R.
	T. R.
2. Property Controlling in section	S. T. R.
	S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
REGISTER OF DEEDS STAMP & FILE NUMBER

INERO 007 PAGE 14

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 80.00 SET POST COR. SECS 32 & 33
BEECH 10 N 61 1/2 E 56
BEECH 10 N 37 1/4 W 40
- D. RATEKIN, L.C.R.C. RECORDED IN L 2, P. 22, DATED: 09-18-72
(SAME INFORMATION ON SURVEY RECORDED BY RATEKIN, L. 899, P. 325, DATED: 04-14-76))
1/2" PIPE
-30" OAK NORTH 4.0'
-12" CHERRY S45°E 28.1'
-7" CHERRY WEST 33.6'
-22" BEECH N30°W 46.0'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. [Signature]

3. WIGHTMAN MOORED, INC., SECTION CARD INFORMATION
MEASURED DISTANCE BETWEEN E-13 AND F-13 IS 2650.5' +/-

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE PER NUMBER 2 AND 3 ABOVE.
MEASURED DISTANCE BETWEEN E-13 AND F-13 IS 2649.13' (RATEKIN 2650.5' +/-)
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON NOV. 24, 1998

TOTAL OFF ROAD TRAVERSING = 2608.93'
BEARING & DIST. FROM E-13 TO F-13 = N 87°-51'-18" E 2649.13'
BEARING & DIST. FROM E-13 TO D-13 = N 88°-52'-46" E 2608.93'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- NAIL & TAG IN 26" BIRCH N20°W 47.37'
 - NAIL & TAG IN 24" OAK N30°E 5.32'
 - NAIL & TAG IN 8" OAK S10°W 8.63'
 - NAIL & TAG IN 10" CHERRY N75°W 34.06'
 - IN FENCE LINE TO THE EAST, WEST & NORTH

Raymond Moored Date 12/1/98

Surveyors License No. 26463

