

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

19980007 P/ED 15

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>-12W</u>	F-1
	T _____ R _____	N 1/4 Sec-4
	T _____ R _____	Otsego Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

FILED
1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Basil Address, in a field survey on December 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O.

This position was not established by G.L.O.

- 12 Feb 80 D.A. Ratekin, C.S.
L.C.R.C. L-003, P-289
- Part - "C"
- Iron over stone
- 18" Oak N 20° E 44.65'
- PP S 30° W 76.06'
- 18" Oak N 80° E 87.16'
- St. Sign SE 34.02'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 12-8-1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Fd on Twp Line
1" iron over stone w/plow pt. 2' +/- deep
- 38" Oak N 20° E 44.6' +/-
- PP S 30° W 76.6' +/-
- 38" Oak N 80° E 88.5' +/-

Grouted Std A.C. Mon (3/4" iron w/remon cap) over 1" iron, stone and plow pt.
This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Approved by Allegan Co. Peer Group 8 December 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Std A.C. Mon
16 d & Remon Tag SW Sde PP S 70° E 183.01'
16 d & Remon Tag SE Sde 38" Oak N 70° E 88.53'
16 d & Remon Tag SE Sde 38" Oak N 20° E 44.99'
16 d & Remon Tag NW Sde PP S 30° W 76.66'
Std A.C. Mon (F-13, T-2N, R-12W) East 44.5'
In c/l 112th Ave (Gravel) +/-
In Line W/ c/l 19th St. (Bit) to South



Signed by [Signature] Date 30 DEC 98
Surveyor's Michigan License No. 30075