

SURVEY  
REMONUMENTATION

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBER 007 PAGE 16

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 1N R. 12W	F-13
S 1/4 CORNER COMMON TO SECTION 33	T. .... R. ....	.....
OTSEGO TOWNSHIP	T. .... R. ....	.....
	T. .... R. ....	.....
2. Property Controlling in section	S. .... T. .... R. ....	.....
	S. .... T. .... R. ....	.....
3. Miscellaneous Property in Sec.	S. .... T. .... R. ....	.....
4. Lot No. ...., Recorded Plat. ....		
5. Private Claims. ....		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO-40.00 SET QR SEC. POST  
ELM 13 N 67 1/4 E 61  
ELM 7 N 84 1/2 W 20
- D. RATEKIN, RECORDED L.C.R.C., LIBER 2, PAGE 22, DATED: 09-18-72  
(RATEKIN USED SAME INFORMATION RECORDED L.C.R.C., L. 2, P. 409, DATED: 11-08-74)  
MODEL "T" AXLE  
-6" & 8" TWIN MAPLE N40°E 8.2'  
-10" OAK N30°E 18.0'  
-3" OAK S70°E 11.75'
- WIGHTMAN MOORED, INC., SECTION CARD INFORMATION  
FRONT AXLE  
-6"-8" TWIN MAPLE N40°E 8.2'  
-10" OAK N30°E 18.0'  
-3" OAK S70°E 11.75'  
-DISTANCE BETWEEN E-13 & F-13, 2650.5' +/-

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED Nov. 24, 1998  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND MODEL "T" FRONT AXLE PER NUMBER 2 & 3 ABOVE.  
MEASURED DISTANCE BETWEEN E-13 AND F-13 IS 2649.13' (RATEKIN 2650.5' +/-)

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON NOV. 24, 1998  
TOTAL OFF ROAD TRAVERSING = 2649.13'

BEARING & DIST. FROM F-13 TO E-13 = N 87°-51'-18" E 2649.13'  
BEARING & DIST. FROM F-13 TO G-13 = N 88°-34'-36" E 2605.57'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- NAIL & TAG IN N SIDE 8" OAK S40°E 11.63'
  - NAIL & TAG IN N SIDE 6" OAK S83°E 5.52'
  - NAIL & TAG IN NW SIDE 18" TW MAPLE N78°E 9.31'
  - NAIL & TAG IN W SIDE 18" OAK N15°E 18.67'

[Signature]

Date 12/1/98

Surveyors License No. 26463

