

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code -#
1. Public Land Survey	T <u>-1N</u> R <u>-12W</u>	G-1
	T _____ R _____	NE Sec-4
	T _____ R _____	Otsego Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED

1/28/1999 2:44:39 PM

JOYCE A. MATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBRO 007 PAGE 17

I, Basil Andress, in a field survey on December 10, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
North 78.18 (5159.88) Bet'w Sec's - 3 & 4 (43.56') Intersect N. Boundary 66 lks W of Cor & Set Post Sec's - 3 & 4 W. Oak 22 S 66 E 59 Beech 18 S 78 W 48

Cont. on back of certificate

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd
3/4" iron 0.12' N of Twp. Line
- Fd N & T N. sde PP S 45° W 88.0 +/-
- 6"-10"-10" Triple Elm S 45° E 71.0 +/-
- 10" Oak N 50° E 69.7'+/-
- G-13 (Fd Bent 3/4" iron) East 43.50'
- Fd 1/2" iron SE 62.60'
- Fd 1/2" iron SE 119.56'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 12-8-98
COUNTY REP. [Signature]

Set Std A.C. Mon (3/4" x 24" iron W/Remon Cap) 43.50' West of G-13 and on Twp. Line. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Approved by Allegan Co. Peer Group 8 December 98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Std. A.C. Mon.
- 16 d Remon Tag NW Sde 6"-10"-10" Elm S 35° E 70.57'
- 16 d & Remon Tag N'ly Sde PP S 55° W 87.83'
- 16 d & Remon Tag SW Sde 6" Ash N 45° W 39.16'
- 16 d & Remon Tag SE Sde 6"-12"-12" Oak N 30° E 36.55'
- Std A.C. Mon (G-13, T-2N, R-12W) East 43.50'
- c/1 112th Ave. (Gravel) N 2' +/-
- In line W/ c/1 18th St. (Gravel) to South



Signed by Basil Andress Date 30 DEC 98
Surveyor's Michigan License No. 30075

G-1 OTSEGO TWP.

SURVEY
REMONUMENTATION

A. Continued

APR 29 1933

1969 D.A. Ratekin C.S.
Witness Card Sec-4
Set 1" iron
St. Sign NNE 25.05
15" Oak NE 57.55

SECTION

Witness Card Sec-3
(G-1) to (G-2) Meas 2527.70'
(G-2) to (G-3) Meas 2648.20'
Shows 180° @ G-2

9 Oct 92 Wightman-Moored
Survey for A.C.R.C. Rd Proj.

Fd 3/4" iron
- PP S 45° W 88.04'
- 6" Triple Elm S 45° E 70.96'
- 6" Oak N 50° 69.68
- G-13 N 89° - 49 - 45 W 43.63
- 1/2" iron S 54° - 46' - 08" E 62.61
- 1/2" iron S 54° - 46' - 08" E 119.55