

SURVEY  
REMONUMENTATION

APR 29 1999

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

ALLEGAN COUNTY REGISTER OF DEEDS

FOR CORNERS IN: ALLEGAN COUNTY

LOCATED IN: CORNER CODE #

1. Public Land Survey T. 1N R. 12W G-13

SECTION COR. COMMON TO SECTION'S 33 & 34 OTSEGO TOWNSHIP

2. Property Controlling in section S.....T.....R.....

3. Miscellaneous Property in Sec. S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
80.00 SET POST COR. SECS 33 & 34  
SUGAR 26 N 41 E 10  
BEECH 16 N 43 1/2 W 57

\* NO OTHER CORNER HISTORY \*

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV. 24, 1998  
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON  
MEASURED DISTANCE BETWEEN G-13 & H-13 = 2640.025'  
MEASURED DISTANCE BETWEEN F-13 & G-13 = 2605.57'  
SET 3/4" X 2 1/4" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV. 24, 1998  
TOTAL OFF ROAD TRAVERSING = 2605.57'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL & TAG IN SE SIDE 12" CHERRY NORTH 1.21'  
-NAIL & TAG IN S SIDE 16" CHERRY N89°E 17.53'  
-NAIL & TAG IN S SIDE 12" CHERRY S44°W 15.17'  
-NAIL & TAG IN W SIDE 6" OAK S30°E 15.09'  
-E & WEST FENCE LINE SOUTH 2'  
-ON LINE WITH FENCE TO NORTH

*[Signature]* Date 12/1/98

Surveyors License No. 26463

