

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SECTION

FILED

FOR CORNERS IN: ALLEGAN COUNTY
LOCATED IN: CORNER CODE #

1/28/1999 2:44:39 PM

- 1. Public Land Survey T.....1N R.....12W H-13
S 1/4 CORNER COMMON TO SECTION 34
OTSEGO TOWNSHIP T..... R.....
T..... R.....
- 2. Property Controlling in section S.....T.....R.....
S.....T.....R.....
- 3. Miscellaneous Property in Sec. S.....T.....R.....
- 4. Lot No.....Recorded Plat.....
- 5. Private Claims.....

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

LIBR0007 PAGE020

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		5		4		3		2		1
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
40.00 SET QR SEC. POST
B ASH 15 N 75 2/3 E 108
ELM 15 N 25 E 100

* NO OTHER CORNER HISTORY *

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION.
ESTABLISHED CORNER POSITION MIDWAY AND ON LINE BETWEEN G-13 AND I-13 (2640.025')
SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON NOV. 24, 1998
TOTAL OFF ROAD TRAVERSING = 5280.05'

BEARING & DIST. FROM H-13 TO I-13 = N 89°-04'-05" E 2640.025'
BEARING & DIST. FROM H-13 TO G-13 = N 89°-04'-05" E 2640.025'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN W SIDE 18" ELM S5°W 23.18'
-NAIL & TAG IN N SIDE 6" MAPLE N80°W 1.25'
-NAIL & TAG IN SW SIDE 10" MAPLE S85°E 17.41'
-NAIL & TAG IN N SIDE 22" ELM S40°W 58.75'
-CIL DITCH NORTH 14'

Raymond Moored Date 12/1/98

Surveyors License No. 26463

