

**SURVEY
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SECTION

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBER0007 PAGE021

| | | |
|--|-------------------------|---------------|
| FOR CORNERS IN: ALLEGAN COUNTY | LOCATED IN: | CORNER CODE # |
| 1. Public Land Survey | T. 1N R. 12W | I-13 |
| SECTION COR. COMMON TO SECTION'S 34 & 35 OTSEGO TOWNSHIP | T. R. | |
| | T. R. | |
| | T. R. | |
| 2. Property Controlling in section | S. T. R. | |
| | S. T. R. | |
| 3. Miscellaneous Property in Sec. | S. T. R. | |
| 4. Lot No., Recorded Plat | | |
| 5. Private Claims | | |

REGISTER OF DEEDS STAMP & FILE NUMBER

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 8 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 80.00 SET POST COR. SECS 34 & 35
ELM 12 N 55 1/4 E 25
B ASH 12 N 16 1/2 W 42
- D. RATEKIN, SURVEY RECORDED IN L. 794, P. 58, DATED: 07-15-71
(SAME INFORMATION ON L.C.R.C. RECORDED BY RATEKIN, L. 1, P. 64, DATED: 07-29-71)
STONE POINT
-8" ASH N25°E 8.1
-9" ASH N25°W 8.3
-C/L DRAIN NORTH 9.5
-IN EAST & WEST FENCE
- WIGHTMAN MOORED, INC., SECTION CARD INFORMATION
DRAIN DUG & CLEARED 10/71
-40" DEAD ELM N 41.2'
-30" MAPLE S85°W 115.9'
-C/L DRAIN NORTH 14.5'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 24, 1998
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON IN PLACE OF STONE POINT PER NUMBER 2 ABOVE.
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON NOV. 24, 1998.
TOTAL OFF ROAD TRAVERSING = 0
I-13 TO J-13 = N 88°-56'-00" E 2633.55'
I-13 TO H-13 = S89°-04'-05"W 2640.025'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
- NAIL & TAG IN E SIDE 10" MAPLE S85°W 15.48'
 - NAIL & TAG IN E SIDE 10" OAK S30°W 20.08'
 - NAIL & TAG IN SW SIDE 10" OAK S40°E 17.13'
 - NAIL & TAG IN SW SIDE 6" OAK N89°E 12.28'
 - C/L DITCH NORTH 13.52'

[Signature: Raymond Moored]

Date 12/16/98

Surveyors License No. 26463

