

COMMISSION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN  
(County)

Located in:

Corner Code #

- |                                       |                            |  |
|---------------------------------------|----------------------------|--|
| 1. Public Land Survey                 | T <u>1</u> N R <u>12</u> W | <u>J-7 (S<math>\frac{1}{2}</math>, 14)</u> |
|                                       | T _____ R _____            | <u>Osseo</u>                               |
|                                       | T _____ R _____            | _____                                      |
|                                       | T _____ R _____            | _____                                      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____    | _____                                      |
|                                       | S _____ T _____ R _____    | _____                                      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____    | _____                                      |
|                                       | S _____ T _____ R _____    | _____                                      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1993 DEC 30 PM 2:41  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.  
 David F. Peabody

FILED

Register of Deeds Stamp & File Number

I, David F. Peabody, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- |                    |                                       |
|--------------------|---------------------------------------|
| G.L.O. (Stone W/X) | Donald Ratekin (County Surveyor) 1972 |
| W. Oak 17 N64E 42  | LCRC L.1, P.197                       |
| W. Oak 17 S73W 9   | Found 1" Iron Set by Same             |
|                    | CL Fire Hydrant N35°E 26.78'          |
|                    | SE Corner Catch Basin N25°W 42.48'    |
|                    | E. Corner Catch Basin N55°W 37.98'    |
|                    | CL Manhole S15°W 15.80'               |
|                    | SW Cor. Catch Basin North 31.63'      |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron  
G.L.O. All Gone  
All Donald Ratekin 1972 Accessories were located & used  
This Corner is accepted as a careful and faithful reestablishment of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed Remon Cap over 1" Iron  
C.L. Fire Hydrant N50°E 26.78'  
C.L. Manhole S25°W 15.80'  
SW Corner Catch Basin N10°E 31.63'  
SE Corner Catch Basin N18°W 42.48'  
E. Corner Catch Basin N55°W 37.98'  
20d Nail W/Allegan Co. Tag NE Side Power Pole N12°W 70.93'  
20d Nail W/Allegan Co. Tag SE Side Power Pole S45°W 33.01'  
C.L. Road South 4' ±  
8' East of C.L. Fairview Street To North



Signed by David F. Peabody Date 12/20/93  
Surveyor's Michigan License No. 25866