

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

FILED

1/28/1999 2:44:39 PM

LIBRO 007 PAGE 22

SECTION

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey LOCATED IN: CORNER CODE #

S 1/4 CORNER COMMON TO SECTION 35 OTSEGO TOWNSHIP

T. 1N R. 12W J-13

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat

5. Private Claims

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 40.00 SET QR SEC POST
-B. ASH 13 N63W 51
-B. ASH 22 N32 1/2E 88

* NO OTHER CORNER HISTORY FOUND *

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 8, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION
SET 1/2 WAY AND ON LINE BETWEEN I-13 AND K-13
I-13 TO J-13 = N88°-56'-00"E 2633.55' J-13 TO K-13 = N88°-56'-00"E 2633.55'
DISTANCE BETWEEN J-13 (OTSEGO TWP) AND I-1 (ALAMO TWP) = 245.07'
SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 08, 1998
TOTAL OFF ROAD TRAVERSING = 2633.55'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN N SIDE 18" TW ELM S80°E 48.81'
-NAIL & TAG IN E SIDE 18" TW ELM N10°W 11.68'
-NAIL & TAG IN N SIDE FENCE POST S70°W 8.29'
-NAIL & TAG IN N SIDE 8" APPLE S85°W 22.01'

[Signature]

Date 12/16/98

Surveyors License No. 26463

