

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
 (County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>1</u> N R <u>12</u> W	<u>K-7 (SW,13)</u>
	T ___ R ___	<u>Otsego</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

1993 DEC 30 PM 2:41
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Gregory D. LeBrette

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David F. Peabody, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


G.L.O. (Set Post)	Gary Bilow (MDNR) 1990
W. Oak 14 S25W 11	LCRC L.04, P.102
W. Oak 16 N59E 8	Found 1" Iron Bar
	S35°E 12.04' Set Nail & MDNR Tag NE Face Guy Pole
Donald Ratekin (County Surveyor) 1992	S22°E 86.30' Top Center Hydrant
Found 1" Iron (LCRC L.1, P.203)	South 167.9' North Edge North Rail of Railroad
P. Pole N30°E 31.7'	S63°W 24.94' Set Nail & MDNR Tag N. Face P.P. W/Trans.
Guy Pole S30°E 11.6'	East 7' ± Approx. CL Hill Road (Gravel)
P. Pole S55°W 24.6'	
CL Hill Street 8.0' West	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" Iron
 P. Pole N30°E 31.7'
 Guy Pole S30°E 11.6'
 CL Hill Street 8.0' West
 All Gary Bilow Accessories were located & used
 This Corner is accepted as a careful and faithful reestablishment of the position of the Original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Remon Cap over 1" Iron
 Nail W/MDNR Tag NE Face Guy Pole S35°E 12.04'
 Top Center of Hydrant S22°E 86.30'
 North Edge North Rail of Railroad South 167.9'
 Nail W/MDNR Tag N. Face Power Pole W/Transformer S63°W 24.98'
 20d Nail W/Allegan Co. Tag NW Side Power Pole N32°E 32.08'
 C.L. Hill Road 7' ± West



Signed by David F. Peabody Date 12/20/93
 Surveyor's Michigan License No. 25866