

**SURVEY
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

SECTION

FOR CORNERS IN:	LOCATED IN:	CORNER CODE #
ALLEGAN COUNTY		
1. Public Land Survey	T.1N..... R.12W.....K-13.....
SEC. COR. COMMON TO SECTION'S 35 & 36 OTSEGO TOWNSHIP	T..... R.....
	T..... R.....
	T..... R.....
2. Property Controlling in section	S.....T.....R.....
	S.....T.....R.....
3. Miscellaneous Property in Sec.	S.....T.....R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
REGISTER OF DEEDS STAMP & FILE NUMBER

LIBERO 007 PAGE 23

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
80.00 SET POST COR. SECS 35 & 36
BEECH 20 N64E 47
W ASH 18 N56W 80

* NO OTHER CORNER HISTORY *

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC 8, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION.
SET ON OCCUPATION LINE TO NORTH AND ON EXT. OF LINE FROM I-13 OF OTSEGO THRU I-1 OF ALAMO.
SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON DEC. 08, 1998
K-13 TO L-13 = N 89°-31'-34" E 2614.08' K-13 TO J-13 = N 88°-56'-00" E 2633.55'
I-1 (ALAMO TWP.) TO J-13 (OTSEGO TWP.) = N 88°-56'-00" E 245.07'
TOTAL OFF ROAD TRAVERSING = 2633.55'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP
-NAIL & TAG IN SE SIDE POWER POLE S75°W 30.64'
-NAIL & TAG IN SE SIDE 6" OAK S85°W 47.53'
-NAIL & TAG IN N SIDE 6" MAPLE N85°W 48.32'
-C/L DRAINAGE DITCH SOUTH 1' +/-

Raymond Moored

Date 12/16/98

Surveyors License No. 26463

