

MAR 1 6 1994

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CONTELESSION
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 1 N R 12 W	L-7 (St. 13)
	T ___ R ___	Ossego
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

Register of Deeds
ALLEGAN COUNTY, MICH.

1993 DEC 30 PM 2:41

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, David F. Peabody, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. (Set Post) Gary Bilow (MDNR) 1990
 - Butternut 14 N27E 47 LCRC L.4, P.97
 - Beech 22 S45W 55 Fd. 3/4" Iron Bar
 - Donald Ratekin (County Surveyor) 1974 South 99.8' North Edge of North Rail of Railroad
 - Fd. 3/4" Iron N70°W 12.03 Set Nail & MDNR Tag NE Face 18" Oak
 - 14" Oak WNW 11.9' S8°E 4.26' Set Nail & MDNR Tag NW Face Cherry
 - Fence Line W. 10.6' N5°W 50.48' Set Nail & MDNR Tag E'LY Face 20" Oak
 - 18" Oak NNW 49.25'
 - CL Railroad Grade S'LY 100' ± (LCRC L.2, P.249)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- All Donald Ratekin 1974 Accessories were located & Used
 - All Gary Bilow 1990 Accessories were located & used
 - Found 3/4" Iron
 - This Corner is accepted as a careful and faithful reestablishment of the position of the Original Corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Placed Remon Cap over 3/4" Iron
 - North Edge of North Rail of Railroad South 99.8'
 - Nail W/MDNR Tag NE Face 18" Oak N70°W 12.03'
 - Nail W/MDNR Tag NW Face Cherry S8°E 4.26'
 - Nail W/MDNR Tag E'Ly Face 20" Oak N5°W 50.48'
 - 20d Nail W/Allegan Co. Tag NW Side 8" W. Cherry S35°W 34.12'



Signed by David F. Peabody Date 12/20/93
 Surveyor's Michigan License No. 25866

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983