

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 1 N R 11 W A-13 (SW, 31)
T _____ R _____
T 1N R 12W M-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

M-13
OT 5660

1994 JUN -3 PM 1:17
Register of Deeds Stamp & File Number

FILED

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David F. Peabody, in a field survey on March 01, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - G.L.O. (set post) Donald A. Ratekin (County Surveyor) 1972
 - Birch 8 N25W 41 23" Elm N. 22.8'
 - Sugar 7 N32 1/2 E 70 SE Cor of house NW 87.8'
 - 24" Elm WNW 49.2'
 - 32" Elm WNW 77.8'
 - 1" Iron (Boat Spike)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - Found Boat Spike in Monument Box
 - SE Cor of house NW 87.8'
 - Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 4-12-94
COUNTY REP. David F. Peabody

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - Removed Boat Spike and placed 3/4" Iron W/Remon Cap in Monument Box
 - Face 6" Spruce N45°W 34.2'
 - 20d nail W/Allegan Co. Tag E. Side P. Pole N. 64.00'
 - 20d nail W/Allegan Co. Tag NW Side P. Pole S15°W 105.40'
 - 20d nail W/Allegan Co. Tag NE Side T. Pole S60°E 81.11'
 - 20d nail W/Allegan Co. Tag N. Side 14" Maple N70°W 90.44'
 - Corner of House N40°W 87.78'



Signed by David F. Peabody Date 5/10/94
Surveyor's Michigan License No. 25866