

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan County
(County)

Located In:

Corner Code \neq

1. Public Land Survey		1N	12W	K-7
	T	_____	R _____	_____
	T	_____	R _____	_____
	T	_____	R _____	_____
	T	_____	R _____	_____
2. Property Controlling in Section	S	_____	T _____	R _____
	S	_____	T _____	R _____
3. Miscellaneous	S	_____	T _____	R _____
Property in Sec.	S	_____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Gary C. Bilow, in a field survey on March 6, 1990

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-7) Corner recorded by D. A. Ratekin, RLS 8781, April, 1972, as Found 1" iron (L.C.R.C. L.1 - P.203)

- P. Pole N30°E 31.7'
- Guy Pole S30°E 11.6'
- P. Pole S55°W 24.6'
- ‡ Hill Street 8.0' West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-7) Found and accepted 1" iron bar 11" below surface. Ratekin accessories to guy pole and P. Pole SW check

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K-7) Found 1" iron bar

- S35°E 12.04' Set nail and MDNR tag NE face guy pole
- S22°E 86.30 Top center hydrant
- South 167.9' North edge north rail of railroad
- S63°W 24.94' Set nail and MDNR tag in N. Face P/P with transformer
- East 7' ‡ approximate ‡ Hill Road (gravel)



Signed by Gary C. Bilow Date 3/1/91
 Surveyor's Michigan License No. 26453