

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan

(County)

Located In:

Corner Code ##

1. Public Land Survey

T 1N R 12W

C-6

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Gary C. Bilow

March 6

19 90

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C-6) Corner recorded by D. A. Ratekin, LS 8781 in 1978, who perpetuated old pointed stake in swamp with 1/2" pipe with cap. Rec. accessories:

- Nail S. side 6" Elm, E. 23.68'
- Nail S. side 16" Basswood, N60°W 21.11'
- Nail N. Side 12" Ash, S75°W 21.84'
- 140' E of Foot of Hill

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-6) Found and accepted 1/2" pipe with cap # 8781. Ratekin accessories to Basswood and Ash check

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-6) Found 1/2" Pipe with cap # 8781

- N50°W 21.11' Nail and Tag S. Face 16" Basswood
- S48°W 19.10' Nail and Tag SE Face 6" Ash
- S73°W 21.82' Nail and Tag N Face 12" Ash
- S58°W 0.5' Iron Fence Post



Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 3/8/91