

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>12W</u>	<u>D-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gary C. Bilow, in a field survey on March 29, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner restored by single proportionate measure by David R. Greer RLS # 16042  
 Feb. 22, 1983 and recorded in L.3, P.361  
 Record monument and accessories:  
 1/2" Steel Rod  
 P.P. S70°W 75.72'  
 30" Maple South 101.42'  
 30" Maple S20°E 65.51  
 SW Cor. of Dam Headwall N80°E 93.61'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered accessories as recorded but did not find 1/2" steel rod. Also noted quadrant error in tie to headwall. Re-established corner position from above accessories and monumented position with 1/2" x 36" rebar encased in 4" dia. concrete cylinder capped with cast aluminum Michigan Department of Natural Resources tablet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" Dia. concrete monument with MDNR Cap  
 S70°W 75.72' P.P.  
 South 101.42' 30" Maple  
 S20°E 65.61' 30" Maple  
 N80°W 93.61' SW Cor. of dam headwall  
 N12°E 25.0' W. end chain link fence (post)  
 West 110.00' Set 4" Dia. concrete mon. with MDNR Cap on line between D-7 and C-7



Signed by Gary C. Bilow Date 3/8/91  
 Surveyor's Michigan License No. 26453