

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>12W</u>	<u>E-5</u>
	T <u>1N</u> R <u>12W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on March 29, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (E-5) Corner recorded by D.A. Ratekin, RLS 8781 in L.1, P.201 as found 1/2" iron over brass cap. Rec. accessories: RR spike in W. root 36" Maple N55°E, 42.7'; 42" Oak N20°W, 77.4'; RR tie fence corner post S05°W, 30.95'
- (E-7) Corner recorded by D. A. Ratekin in L. 1, P. 359 as found 1/2" pipe Rec. accessories: Fence cor. post N60°E, 1.55'; 5" Sassafrass N10°W, 2.7'; P. Pole S40°E, 43.65

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (E-5) Found 1/2" Iron Bar. Ratekin tie to post checks. Tie to Maple checks to 35' Oak
- (E-7) Found and accepted 1/2" pipe, Ratekin's ties to Sassafrass and P. Pole check

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| (E-5) Found 1/2" Iron Bar
N59°E 44.00' Spike in 35" Oak
N27°W 61.52' Set Spike and MDNR
Tag in 14" Oak
S64°E 72.60' 60d Nail and MDNR
Tag in 38" Oak
South 4.4' Centerline E-W Road | (E-7) Found 1/2" Iron Pipe
N10°W 2.7', 5" Sassafrass
S40°E 44.08', Set Nail and Tag
In P. Pole
N58°E 14.2' SW Cor. Pole Bldg.
West 0.5' Steel Fence Post |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Signed by Gary C. Bilow
 Surveyor's Michigan License No. 26453

Date 3/8/81

