

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

— <u>Allegan County</u> —	Located In:	Corner Code <u>—//</u>
1. Public Land Survey	T 1N R 12W	B-6
	T 1N R 12W	B-7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on March 6, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	●	17	16	15	14	13						
7	●											
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(B-6) Corner not established in original survey. Allegan County Surveyor S.W. Hicks states in record dated June 10, 1885, "commenced at S1/4" post and run N. on 1/4 line to N 1/4 post. 1/4 post sets in Kalamazoo River. Determined its position from the meander post on E. bank of River. Meander post 50 links, E. of 1/4 post. Made a witness for stake on left high bank of river. R. Oak 30 S74 1/2° E 57. Set stakes along line at 10.0 c."

(B-7) Corner recorded by D. A. Ratekin, 1973 as "found old corner fence post—fence N-W & E. Set 1" iron on E. side of cor. fence post (see L.C.R.C. 1.2 - p.150)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-6) Found no monumentation at corner location. No evidence of meander corner east of N 1/4 corner or of GLO or Co. Surveyor accessories to same. Found remains of old N-S wire fence all on ground and on line between B-7 and computed position of B-5 based on prorated GLO record along N line Sec. 17. Believe this fence to be perpetuation of old county surveyor 1/4 line. Set 1/2"x36" long re-rod encased in 4" dia. Concrete cylinder with cast aluminum Mich. Dept. of Natural Resources cap at intersection of straight lines connecting opposite 1/4 corners and in remains of old N-S fence. Found 1 1/2" iron pipe 53' East and 67' North of this location in an old fence intersection E-S-NNE.

(B-7) Found and accepted 1" iron bar. Ratekin tie to Maple checks but is dead. Ratekin tie to 9" Cherry checks to 16" Cherry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-6) Set 4" Dia. concrete monument with MDNR cap
 S77° E 22.76' Set nail and MDNR tag E.
 Face 7" Silver Maple
 S23° E 5.08' Set nail and MDNR tag E.
 Face 12" Ash
 S25° W 16.00' Set nail and MDNR tag E.
 Face 5" Ash
 N34° W 16.40' Set nail and MDNR tag
 NE Face 11" Maple
 N38° E 85.77' Found 1 1/2" iron pipe

(B-7) Found 1" iron bar
 S80° W 18.04' Set nail & MDNR tag NE
 Face 16" Cherry
 N40° W 29.15' Set nail & MDNR tag NE
 Face 10" Cherry
 N15° W 22.95' Set nail & MDNR tag
 SW Face 10" Ash
 S31° W 28.05' Set nail & MDNR tag
 W Face 9" Ash

Signed by Gary C. Bilow Date 8/28/99
 Surveyor's Michigan License No. 26453

